



CAPPING BEAM SCHEDULE				
MARK	SIZE	REINFORCEMENT		
		BOTTOM	TOP	SIDE
CB1	900W x 600D	N16	N16	N16
CB2	1500W x 800D	N16	N16	N16
CB3	1500W x 600D	N16	N16	N16
CB4	900W x 1750D	N16	N16	N16

NOTE:
REFER TO DETAILS ON S008 FOR SHEAR LIG REINFORCEMENT AND SPACING.